



त्रिभुवन विश्वविद्यालय
Tribhuvan University

Ph. No. +977-014244047

त्रि-चन्द्र बहुमुखी क्याम्पस Tri-Chandra Multiple Campus



स्थापित : १९७५ वि.सं. / Estd. 1918 A.D.

क्याम्पस प्रमुखको कार्यालय
Office of the Campus Chief

पत्र सङ्ख्या / Ref. No. :




सरस्वती सदन, घण्टाघर, काठमाडौं, नेपाल
Saraswati Sadan, Ghantaghar, Kathmandu, Nepal

मिति - २०८२/१०/२९

विषय :- कोटेशन आव्हान सम्बन्धि सूचना ।

उपरोक्त विषयमा यस क्याम्पसको विज्ञान भवनको माइक्रोवायोलोजी विभागको प्रयोगशालाबाट पानी चुहिएर तल तलाको वनस्पतिशास्त्र विभागको प्रयोगशालामा कार्य गर्न समस्या भएकोले सो मर्मत कार्यको लागि यस क्याम्पसमा इजाजत प्राप्त सूचकृत सप्लायर्स तथा निर्माण कम्पनीहरूबाट (असात) दिन भित्र यसै साथ संलग्न BOQ फाराम भरी कार्यालय समय भित्र दर रेट पेश गर्न यो सूचना प्रकाशित गरिएको छ । विस्तृत जानकारीका लागि यस क्याम्पसको सामान्य प्रशासन शाखामा सर्म्पर्क राख्नु हुन समेत जानकारी गराईन्छ ।


.....
प्रा.डा. निलम श्रेष्ठ प्रधान
क्याम्पस प्रमुख
क्याम्पस प्रमुख
त्रि-चन्द्र बहुमुखी क्याम्पस

Name of Work: Renovation Work of Microbiology and Zoology Labs
Location: Tri-Chandra Multiple Campus

BILL OF QUANTITY

S.N.	Description	Unit	Quantity	Rate		Amount	Remarks
				In Figure	In Words		
1.0	Site clearance: Clearance of working site before and after the work, removing furniture and other items safely and replacing those items in the same place after waterproofing works complete, fittings of the pipes, removal of dust and debris from site to appropriate location as per direction of site incharge, all complete works.	Ls	1.00				
2.0	Surface Chipping: Chipping and roughining of existing screed/punning surface using appropriate hand tools to obtain properly roughened surface including removal of loose particles, cleaning dust and laitance and all the debris shall be collected and disposed from site. The site shall be cleared before and after the work, removal of unnecessary materials, removal from site to appropriate location as per direction of site incharge, all complete works.	Sqm	114.33				
3.0	Water Proofing: Providing and applying polymer modified acrylic base two component (Sika top seal 107 / Dr. fixit pidilin 2K) flexible waterproofing coating in two layers applied in horizontal and vertical strokes when each coat is in tacky condition over the prepared RCC slab and on the vertical surface. After 3 days ponding the area with water for 3 days to test water tightness etc all complete.	Sqm	114.33				

NAME OF CONTRACTOR:-

AUTHORIZED PERSON:

COMPANY SEAL

CONTACT NO./ADDRESS:-

SIGNATURE:-

PAGE NO:-1 OF 3

Name of Work: Renovation Work of Microbiology and Zoology Labs
Location: Tri-Chandra Multiple Campus

BILL OF QUANTITY

S.N.	Description	Unit	Quantity	Rate	Amount	Remarks
4.0	Screeding Work: Providing Cement sand mortar 38 mm thick (1:2:4) concrete screeding as per specification and instruction, all complete work.	Sqm	109.32			
5.0	Plaster Work: 12.5 mm thick cement sand plaster (1:4) on walls and floor and curing all complete work as per instruction.	Sqm	6.33			
6.0	Punning Work: Providing layer of Cement sand mortar 3 mm thick (1:1) concrete punning as per specification and instruction, all complete works.	Sqm	109.32			
7.0	PVC Pipe: Providing and Fixing Lead Free PVC Pipe as per ASTM D 1785, 110mm (4") (15.47 kg/cm ²) to existing rain water pipe with all necessary fittings, clamp, for rainwater drainage from gutter, including all the necessary clamps, screw, etc. all complete work	Rm	25.00			
8.0	PVC Pipe: Providing and Fixing Lead Free PVC Pipe as per ASTM D 1785, 6" (12.66 kg/cm ²) to existing rain water pipe with all necessary fittings, clamp, for rainwater drainage from gutter, including all the necessary clamps, screw, etc. all complete work	Rm	15.00			

NAME OF CONTRACTOR:-

AUTHORIZED PERSON:

COMPANY SEAL

CONTACT NO./ADDRESS:-

SIGNATURE:-

PAGE NO:-2 OF 3

Name of Work: Renovation Work of Microbiology and Zoology Labs
 Location: Tri-Chandra Multiple Campus

BILL OF QUANTITY

S.N.	Description	Unit	Quantity	Rate	Amount	Remarks
8.0	CP Swan Neck Pillar Cock: Providing and fixing 15mm swan neck pillar cock made of heavy-duty brass, chromium plated with smooth glossy finish, complete with all standard accessories such as washer, flange, nuts and fittings, including cutting, threading, fixing, testing for leakage, and making good to walls/floors, all as per approved make and specifications, all complete.	Nos	17.00			
9.0	PVC Flexible Pipe: Providing and fixing flexible connection pipe PVC suitable for wash basin connection, including all fittings, nuts, washers, cutting, jointing, testing, and making good complete as per standard specifications and direction of Engineer	Nos	25.00			
10.0	Emulsion Paint: Providing and painting two coats of emulsion paint over plastered surface of approved color and brand to even and uniform shade including necessary scaffolding, cleaning the surfaces, all complete as per instruction of engineer.	Sqm	109.32			
		Total				
		VAT @13%				
		Grand Total				
Grand Total In Words:						

NAME OF CONTRACTOR:-

AUTHORIZED PERSON:

COMPANY SEAL

CONTACT NO./ADDRESS:-

SIGNATURE:-

PAGE NO.-3 OF 3